Petersfield Festival Hall

RIBA Stage 2 - Design Report Tim Foster

Foster Wilson Architects

Petersfield Festival Hall

Design Proposals are now at the end of RIBA Stage 2 What work has been done and what has changed?

CONSULTATION PROCESS

This involved:

- Presentation at a Town Meeting in April 2018
- Distribution of a leaflet to all residents in May 2018
- A public meeting and exhibition in June 2018
- Consultations with user groups at the public meeting
- Feedback forms completed by all attendees
- Feedback collated by PTC and discussed with FWA in early August



What were the key issues raised by the consultation process?

KEY ISSUES

- Main Hall. Option 2, with a lowered stage and side galleries, was the preferred option, but with the addition of a retractable choir bleacher and a small orchestra pit.
- Foyer and Rose Room. There was concern about congestion in the foyer caused by enlargement of the toilets. It was agreed to look at an extension at the entrance, to provide a more prominent entrance, a more spacious foyer and better toilet provision.
- Town Hall. PTC confirmed they wish to have an enlarged council chamber, a Town Visitor Centre and an office for the Hall management on the ground floor, with the PTC offices and the reopened Small Hall on the first floor.
- A 'Changing Places' Accessible WC was requested in the Foyer.



FWA responded to these requests with revised proposals

KEY CHANGES

- Main Hall. The addition of a retractable choir bleacher and an enlarged floor pit to provide an orchestra pit.
- Foyer and Rose Room. An extension at the entrance, to provide a
 more spacious foyer, better toilet provision and a reconfigured Rose
 Room inside, with a new parking layout outside.
- Town Hall. An enlarged council chamber, a Town Visitor Centre and an office for the Hall management on the ground floor, with the PTC offices and the re-opened Small Hall on the first floor.
- A 'Changing Places' accessible WC in the Foyer.

A preliminary cost report for these changes was submitted and discussed by the Halls Committee in October.



With the main design development issues agreed, the whole Design Team were able to work up their technical proposals.

DESIGN TEAM

Architects/Lead Consultant Foster Wilson Architects

Services Consultants Skelly & Couch

Structural Engineers Conisbee

Theatre Consultants Carr & Angier

Acoustic Consultants Gillieron Scott Acoustic

Design

Quantity Surveyors/Principal Designer Ainsley & Partners

All team members have prepared technical proposals, which have been coordinated into the revised design and included in a new cost plan. A Design Report covering all disciplines was completed in December 2018.



Timeline




1933 also sees the selection of architects Seely & Paget of 41 Cloth Fair London, appointed following an organised competition.



1975 - Petersfield Town Council gain planning permission for the erection of a 'small hall' to the East of the building - currently used as kitchen. This was built by Vic Hallam using his innovative 'Derwent System' Modular building method in 'Type Six'.

1975



1979 - Planning Application is made for a brick extension on the West side of the Festival Hall, containing scene dock and dressing rooms.

.....



1980 - Planning Application is made for the erection of a new side entrance extension, linking the 'small hall' with the Main Hall.



1987 - Petersfield Festival Hall reopens after new extension is built to rear and to the West side by local architect Kenneth Claxton. This was the final phase of his 5 phase scheme originally proposed in 1976.

1933

In January of 1933, Marie Brahms instigates the

need for a new venue

productions. Her efforts

were backed up by local

philanphropist Dr. Harry

for amateur theatre

Roberts.

3

1935 - Town Hall and Festival Hall is

1935

completed in the year 1935 by Messrs. Rigg and Remington, of Carteret House, Westminster. 1976 - Plans are drawn

up for a new phased scheme for the Music Hall including extensions and refurbishment, by local architect Kenneth Claxton.

1976

1979 - Town Hall and Festival

1979

Hall is reopened to the public in October following an extensive refurbishment and side extension built to house scene dock and dressing rooms. The building is renamed Petersfield Festival Hall. 1980 1983

1983 - Approximate time the original Small Hall on the First Floor, is partitioned and divided. 1987

2008 - Fire rips through First Floor Small Hall, which was then used as a costume store. This part of the Town Hall had to be completley

2008

refurbished















Design Proposals

For the purposes of discussion and costing the works are divided into the following zones, which are colour coded on the proposal drawings:


- 1. Extension
- 2. Main Hall
- 3. Backstage
- 4. Foyer and Rose Room
- 5. Entrance Foyer Extension
- 6. Town Hall

Phasing

For current purposes it is assumed the works will be undertaken as a single phase. The possibility of phasing, if required, will be discussed at the next design stage.




Site Plan






Proposed Ground Floor Plan






Proposed First Floor Plan






Elevations 1 & 2





Proposed Elevation 1 (Town Hall Entrance)




Proposed Elevation 2




Elevations 3 & 4





Proposed Elevation 3 (Festival Hall Entrance)



Proposed Elevation 4



Exterior view





Axonometric view





Exterior view






Animation







Main Hall Plan and Section







Main Hall Alternative Layouts 1-4





MUSICAL THEATRE/OPERA WITH ORCHESTRA PIT







SMALL THEATRE




Main Hall Alternative Layouts 5-8












Main Hall Balcony Details








Handrail & Hanger Section- Proposed

Main Hall 3D view / Theatre





Main Hall 3D view / Concert





Main Hall Precedents Galleried Auditoria





King's Place

Kent University





Broadway Theatre Barking

Cost Plan



THE FESTIVAL HALL, PETERSFIELD STAGE 2 CONCEPT ESTIMATE EXECUTIVE SUMMARY

05 December 2018

Forecast costs for each individual Area include for the following: Construction Costs, Professional Fees, Surveys, Client Direct Costs, (e.g. kitchen equipment, furniture allowances), Contingency at 5% of Construction Costs, Design Development at 5% of Construction Costs, and Inflation at 4% per annum. All figures Exclude VAT

Note: Works Priced as a single project - if the works are phased, deferred or carried out as individual separate contracts this will have cost effect and will increase the forecast costs

		Revised @ 30.11.18	Previous Advice 28th September 2018	Comment
NEW EXTENSION	£	1,330,000	£ 1,190,000	Sub-structure & Frame costs increased. Plant deck added. new Surface Water Drainage and attenuation.
ROSE ROOM & LOBBY	£	604,000	£ 488,000	Floor Finish, Ceiling & Acoustic upgrades. Structural works to bar area. Acoustic screen costs moved into Rose Room
NEW FOYER EXTENSION	£	707,000	£ 730,000	Reduced size and parking reduced - offset by new Surface Water Drainage and attenuation. Upgrades to ceiling and acoustic attenuation.
FESTIVAL HALL & BACKSTAGE	£	4,148,000	£ 4,230,000	Rostrum seating individually mechanised. Manual Orchestra Pit. Includes Choir Bleacher
REFURBISH TOWN HALL OFFICE AREAS	£	1,511,000	£ 1,510,000	
TOTAL COST	£	8,300,000	£ 8,148,000	



Preliminary Programme

PETERSFIELD FESTIVAL HALL DESIGN TEAM BY OTHERS CONTRACTOR PRELIMINARY MASTER PROGRAMME 4 / 13/11/2018 KEY: MILESTONES FOSTER WILSON ARCHITECTS 2020 WEEK COMMENCING MONDAY

NOTES

1. PROGRAMME ASSUMES WORKS UNDERTAKEN AS A SINGLE PHASE / FURTHER DISCUSSION OF PHASING REQUIRED

2. PRE AND POST CONTRACT PERIODS SUBJECT TO FURTHER CONSULTATION

3. PROGRAMME SUBJECT TO FUNDING TIMETABLES

4. PROGRAMME ASSUMES A SINGLE STAGE FIXED PRICE CONTRACT WITH COMPETITIVE TENDERING BASED ON A PRICNG SCHEDULE WITH APPX. QUANTITIES



Next Steps

- A further process of consultation will take place over the next 2 months to ensure the proposals meet the needs of users and the wider community.
- Pre-application discussions will be held with the planning authority.
- Design Team to be appointed to develop proposals to RIBA stage 3
 (Developed Design) and to submit a planning application.
- The Council to decide if they wish to undertake the works as a single phase or multiple phases.



Thank You

Foster Wilson Architects